


STEP 2. Remove drawers from base cabinet (see diagram 8) and mount it to the wall panel from interior of cabinet through sides with (3) 3 1/2" hex head bolts. Then mount cabinet to wall with (2) 3" wood screws into wall stud (see diagram 9).




## **Quantity - QTY**


## Finish Schedule - 801-48-1

Face Color - Face Color Top Color - Ledge& Toe Color Toe Color - (Specify) **Pulls - Premium Pulls** Interior - White Melamine Other (Specify) -

## **Installation Notes:**

- 1. All hardware needed for assembly is included.
- 2. Large items are preassembled at the factory to ensure proper alignment. Items are then disassembled into managable sections for shipping purposes and ease of reassembly.
- 3. Shipping cleats need to be removed before installation. These cleats are installed to prevent damage.





# **Quantity - QTY**

### Finish Schedule - 802-66-1

Face Color - Face Color Top Color - Toe-Ledge Color Toe Color - (Specify) Pulls - PREMIUM Interior - Interior Other (Specify) -

### **Installation Notes:**

- 1. All hardware needed for assembly is included.
- 2. Large items are preassembled at the factory to ensure proper alignment. Items are then disassembled into managable sections for shipping purposes and ease of reassembly.
- 3. Shipping cleats need to be removed before installation. These cleats are installed to prevent damage.

